BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Estimate for Desilting of Storm Water Drain in Ward No. 11 (KUvempunagara), Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	12301.25	KSRRB 200-8 : Cleaning and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and tress of girth upto 300mm by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials within a lead of 100 meters from road boundary, labour charges complete as per specifications. MORTH chapter 2. **No. 135 / Item No. 18.11 / PWD SR 2015-16**	Sqm	6.48	
2	6491.25	Excavation and removal of silt or silt mixed with sand in slushy condition from canal bed including jack well disposing off the same in spoil bank or on the canal embankment in layers as directed etc., complete with initial lead upto 50 m and all lifts.MISR 2014-15 (P. 76 / I. No. 44)	cum	245.50	
3	6069.32	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km	cum	103.37	

ಕರಡು ಟೆಂಡರ್ ಪಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....(Nil)
ತಿದ್ದುಪಡಿ ~~ಮಾಡಿ~~ ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

23.9.16

Chief Engineer
Yelahanka Zone
Bruhath Bangalore Mahanagara
Bangalore 92

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

23/9